Final Minor Subdivision Plan

4099 CURLY HILL ROAD

PLUMSTEAD TOWNSHIP, BUCKS COUNTY, PENNSYLVANIA TOWNSHIP FILE NO. 101-375

prepared for

ARTHUR H. ADAMS/JANE K. ADAMS (H/W) TAX PARCEL NO.: 34-003-053-003

prepared by



607 Easton Road Building B - 2nd Floor Willow Grove, PA 19090

Tel: (215) 346-8757 Fax: (215) 346-8759 www.eustaceeng.com

DRAWING NO.	SH	EET
2383 01 01 2383 01 10	1 2	OF OF
2383 01 11	3	OF
2383 01 12	4	OF
2383 01 03	5	OF
2383 01 13	6	OF
2383 01 14	7	OF
2383 01 15	8	OF

PLAN INDEX NAME DATE NO. LAST REVISED 10-27-22 01-05-24 EXISTING CONDITIONS PLAN 01-05-24 OVERALL SUBDIVISION PLAN 01-05-24 SUBDIVISION PLAN - LOT 1 SUBDIVISION PLAN - LOT 2 01-05-24 GRADING & LANDSCAPE PLAN 01-05-24 SITE CONSTRUCTION DETAILS 01-05-24 01-05-24 **EROSION & SEDIMENT CONTROL PLAN** 01-05-24 **EROSION & SEDIMENT CONTROL NOTES & DETAILS** EUSTACE ENG. PROJECT NO. 2383-01



SHEET 1 OF 8



Parcel Information: Tax Parcel No.: 34-003-053-003

Instrument No.: 2021056984

1. Information shown hereon reflects existing site conditions as of August 4, 2021 per a field survey performed by Eustace

2. This plan is to be used for subdivision purposes only. The use of this plan and the information shown hereon for purposes other

4. This property is subject to all easements, restrictions and agreements of record.

5. Easements, if shown, are done so to the best of our abilities given the quality of the reference documents.

10. Precision of information when originally established and typographical errors in legal documentation may result in fractional

differences between what is shown on this plan and the recorded information. 1. To the best of our knowledge this property is served by or has the ability to be served by public electric, and telephone. The location of service connections are unable to be determined. Utility information shown is a composite of information obtained

from the Pennsylvania One Call System Serial Number 20212312548 and field locations by Eustace Engineering. The location of utility features and the feature information is only approximate and where information was readily available. All information is to be verified via a field markout and is subject to the findings that the markout and further research would reveal. Eustace Engineering does not guarantee that all subsurface utility structures and information are shown hereon.

12. This property lies within Flood Hazard Zone-X (areas determined to be outside of 0.2% annual chance flood plain) as per the Federal Emergency Management Agency Flood Insurance Rate Map number 42017C0282J, dated March 16, 2015 for Plumstead

13. Vegetation as shown hereon is approximate and is for graphic depiction purposes only and may not represent exact field locations

14. The location of overhead wires is shown to the best of our ability. Overhead wire heights are not provided. Other than as shown hereon, no aerial services are located on or across the subject properties.

15. No wetlands exist on-site per the evaluation performed by Valley Environmental Services, Inc. dated August 2, 2023. 16. Items shown with an asterisk (*) are; (a) items that are a composite of field data and/or reference material; (b) items not able to be obtained and/or determine due to field conditions. These items are not to be considered absolute and are subject to the

17. Benchmark: Control Point between existing house and existing barn, Elev. 442.70

18. Proposed Lot 1 shall be served by the existing well located east of the existing barn. Proposed Lot 2 shall be serviced by a new well, which shall shall meet the requirements of the Section 22-926. Both proposed lots shall be served by new on-lot septic areas. The installation of the well and septic area on Lot 2 shall be deferred until such time that a building permit is required. 19. The land between the Legal Right-of-Way and Ultimate Right-of-Way is offered for dedication to Plumstead Township as an

20. The requirements of Part 11 - Mandatory Dedication of Recreation Land of the Township's Subdivision and Land Development Ordinance shall be met by a capital contribution in-lieu-of recreation land. 21. Any required approvals and permits for improvements on proposed Lot 2 are deferred as part of a future building permit for any

22. Planting of trees required as part of this subdivision is deferred as part of a future building permit for future construction.

25. Plan North is based on deed bearings recorded in Instrument No. 2021056984, Tax Map Parcel No. 34-003-053-003.



<u>Legend</u>

C

FSBL

Existing Right-of-way Existing Property Line Existing Building

Existing Concrete

Existing Wall

Existing Over Head Wire

Existing Utility Pole Existing Over Head Wire

Existing Edge of Vegetation

Proposed Property Line

Proposed Asphalt Driveway

Proposed Gravel Driveway

Proposed Front Yard Set Back Line

Proposed Rear Yard Set Back Line

Proposed Side Yard Set Back Line

Proposed Natural Resource Set Back Line

400

				NSBL
N/F 60 SILO HILL ROAD 34-003-052-001	N/F 5454 SILO HILL ROAD 34-011-009-002			
	N/F 34-011-009-001	 		
N/F 34-011-009-004	N/F 34-011-009-003			
N/F 5412 SILO HILL ROAD 34-011-008	N/F 5404 SILO HILL ROAD 34-011-009		(GRAPHIC SCALE 0 50 100 200 DRAWING SCALE: 1" = 100'
Site Data: Zoned: RO- Lot Area: 964 954, 940	Rural Residential District ,582.9 S.F. or 22.14 Acres to Title Lir ,557.4 S.F. or 21.91 Acres to Legal Ri ,461 S.F. or 21.59 Acres to Required	ne ight of Way Line Right of Way Line		Overall Subdivision 4099 CURLY HILL

Owner/Applicant:

Arthur Hall Adams/Jane Keelan Adams (H/W) (Husband/Wife) 4099 Curly Hill Rd

SHEET 2 OF 8

all Subdivision Plan CURLY HILL ROAD

PLUMSTEAD TOWNSHIP, BUCKS COUNTY, COMMONWEALTH PA





y		
Total Site Area:	10.51	acres
in Ultimate R-O-Ws:	0.51	acres
Base Site Area:	10.00	acres
nd Resource Protect	ion Area	
Resource	Are	ea
Floodplains (100%):	0.00	acres
odplain Soils(100%):	0.00	acres
rian Buffers (100%):	0.00	acres
s and Ponds (100%):	0.00	acres
and Margins (100%):	0.00	acres
Slopes >25% (85%):	0.31	acres
es 15% - 25% (70%):	1.75	acres
Forest (RO; 80%):	0.36	acres
rce Protection Area:	2.42	acres
est areas have not b	een counted as st	teep slope area
Resource Protection	n - N/A	
Base Site Area:	10.00	acres
red Protected Land:	2.42	acres
Buildable Site Area:	7.58	acres
Base Site Area:	10.00	acres
Maximum Density:	0.50	peracre
er of Dwelling Units:	5.00	
Base Site Area:	10.00	acres
vious Surface Ratio:	25.00	%
Impervious Surface:	2.50	acres
Impervious surface:	0.31	acres
Impervious Surface:	2.19	acres

ole	Allowable	Proposed	Proposed	
ance	Disturbance Area	Disturbance Area	Disturbance	Difference
)	(AC)	(AC)	Ratio	
	0.00	N/A	N/A	N/A
	0.00	N/A	N/A	N/A
	0.00	N/A	N/A	N/A
	0.00	N/A	N/A	N/A
	0.00	N/A	N/A	N/A
	0.05	0.00	0%	0.00
	0.63	0.05	2%	28%
	0.07	0.00	0%	0.00
eas hav	e not heen counte	d as steen slone ar	9.20	



01-05-24

DRAWING No.

2383 01 11

RO - Rural Residential District 964,582.9 S.F. or 22.14 Acres to Title Line 954,557.4 S.F. or 21.91 Acres to Legal Right of Way Line 940,461 S.F. or 21.59 Acres to Required Right of Way Line Owner/Applicant: Arthur Hall Adams/Jane Keelan Adams (H/W) (Husband/Wife) 4099 Curly Hill Rd Doylestown, PA 18902 Parcel Information:

Tax Parcel No.: 34-003-053-003 Instrument No.: 2021056984

SHEET 3 OF 8

SURVEYOR

Dennis R. Dierolf, JR., PLS PA Lic. SU051068E



у		
Total Site Area:	11.63	acres
in Ultimate R-O-Ws:	0.05	acres
ane" Portion of Lot:	0.44	
Base Site Area:	11.14	acres
nd Resource Protecti	on Area	
Resource	Are	ea
Floodplains (100%):	0.00	acres
odplain Soils(100%):	0.00	acres
rian Buffers (100%):	0.00	acres
s and Ponds (100%):	0.00	acres
and Margins (100%):	0.00	acres
Slopes >25% (85%):	0.00	acres
es 15% - 25% (70%):	2.09	acres
Forest (RO; 80%):	0.27	acres
rce Protection Area:	2.36	acres
est areas have not be	een counted as st	eep slope areas
Resource Protection	i - N/A	
Base Site Area:	11.14	acres
red Protected Land:	2.36	acres
Buildable Site Area:	8.78	acres
-		
Base Site Area:	11.14	acres
Maximum Density:	0.50	per acre
er of Dwelling Units:	5.57	
Paca Sita Araa:	11 14	20105
Dase Site Area.	25.00	0/
Impervious Surface	23.00	acres
Impervious Surface:	2.79	acres
Impervious Surface:	0.21	acres
impervious surrace:	2.58	acres

le	Allowable	Proposed	Proposed	
nce	Disturbance Area	Disturbance Area	Disturbance	Difference
)	(AC)	(AC)	Ratio	
	0.00	N/A	N/A	N/A
	0.00	N/A	N/A	N/A
	0.00	N/A	N/A	N/A
	0.00	N/A	N/A	N/A
	0.00	N/A	N/A	N/A
	0.00	0.00	0%	0.00
	0.63	0.30	14%	8%
	0.05	0.00	0%	0.00
ooc how	a not hoon counto	d as stoop slope ar	226	

ZONING DATA TABLE					
REQUIRED	PROPOSED LOT 1	PROPOSED LOT 2			
IING DISTRICT - RO	ZONING DISTRICT - RO	ZONING DISTRICT - RO			
RALRESIDENTIAL	RURAL RESIDENTIAL	RURAL RESIDENTIAL			
DISTRICT	DISTRICT	DISTRICT			
2 Acres	10.00 Acres	11.14 Acres			
200 FT	549.11 FT	742.24 FT			
50 FT	50 FT	50 FT			
40 FT	40 FT	40 FT			
40 FT	40 FT	40 FT			
25%	2.84%	2.01%			
10%	1.00%	N/A			





GR	APHIC	SCALE	E	
0	25	50	100	200
DR	AWING	G SCAL	E: 1" = 50'	



Deals Data Control 526 122		Existing D	itch Capaci	ty	
1. The proposed improvements shall be a	xempt from Peak Rate Control pe	r Shape	1	-	Triangle
 §26-105 C.(2). 1.1. The Applicant/Owner agrees to de 	ed restrict the two (2) proposed	Total Chan Right Side	nel Depth, "E Slope :z1)"	0.86 ft. 0.50 H : V
lots from further subdivision and/c not more than two (2) dwellings.	or restrict future development to	Left Side S Channel sk	Slope: z2 ope, s		3.00 H : V 0.012 ft./ft.
1.2. Lots >10.0 to 20.0 acres are permit area up to 10,000 per Table 26-105	ted a maximum impervious surfaction. 3.3.	ce Manning's 100-YEAR	roughness co	betticient, n	0.070
 The proposed gravel / asphalt area The future owner of Proposed Lot the propulsed aspective for a first formation of the propulsed aspective formation. 	a (impervious area) is 8,603 sf. 2 shall be responsible for acquirin	g Results			1 20 co #
the required permits for any future	e development of said lot.	Wetted per Hvdraulic ra	rimeter, PW adius, r = a/P	W	3.466771 ft. 0.373345 ft.
Volume Control - Neshaminy	Creek - §26-124	V = 1.49*r' Flow Capa	(2/3)*s^(1/2) acity: Qc	/n	1.208582 ft./s 1.56 cfs
rer 926-124 A.(3), the Simplified Metho volume control requirement since the See Simplified Method - Volume Control	ou snan be used to determine the disturbed area is less one (1) acre.	Trough P	ain Con*	I 100:	7.63
Simplified Method - Vo	lume Control	Input Data	ani Capacit I	y	Square
Project: 4099 Curly Hill Road		Bottom Wi	dth, "b" nel Depth. "D) ¹¹ ,	0.82 ft. 0.75 ft.
2-Year Rainfall: 3.26 in		Right Side Left Side S	Slope :z1 lope: z2		1.00 H : V 1.00 H : V
Total Site Area: 0.94 acres Protected Site Area: 0.00 acres		Channel sk Manning's	ope, s roughness co	pefficient, n	0.012 ft./ft. 0.013
Managed Area: 0.94 acres		Possile			
New Impervious Surfaces: 9,080 sqft	4.540	Flow Area	imeter DW		0.62 sq.ft.
Required Permanently Permanent Volume (First 4 in 1	1,913 cutt	Hydraulic r V = 1.49*r	adius, r = a/P (2/3)*s^(1/2)	'W ′n	0.197452 ft. 4.255070 ft./s
Provided Non-Structural BMPs		Flow Capa	acity: Qc	I 100:	2.64 cfs 7.63
Preserved Existing Trees					Existing Duilding
Canopy Area for Trees within 20 feet of Driveway: Volume Reduction:	3,500 sqft 292 cuft				EXISTING RAILOUND
Canopy Area for Trees within 100 feet of Driveway:	5,700 sqft		c	bhw	Existing Over He
Volume Reduction:	237 cuft		3		Existing Edge of
Iotal volume Reduction From Preserved Trees: Difference:	529 cutt -224 cuft		19	95	Existing Index Co
Proposed Trees Proposed Number of Deciduous Trees	9 trees			91	Existing Contour
Volume Reduction:	54 cuft	· · ·	4 	4 4 A	Existing Sidewall
Proposed Number of Evergreen Trees: Volume Reduction:	18 trees 180 cuft	٩	A ·	<u> </u>	ENISTING SILCWOIL
Total Volume Reduction from Proposed Trees:	234 cuft		////		Existing Woodla
Total Provided Non-Structural Volume Reduction:	763 cuft			.//////	
Water Quality - \$26-126			///	////	Existing 15-25%
1. The project is exempt from water qual	lity requirements.		//, \\ x \\		Steep Slopes
			\rightarrow		Existing >25% St Slopes
					Proposed Prope
		_ _ -			Droposed Corre
		<u> </u>	19	<u> </u>	Proposed Grave
					Line Proposed Conto
					Line Proposed Conto Line -
					Line Proposed Conto Line Proposed Storm Conveyance Pip
					Line Proposed Conto Line Proposed Storm Conveyance Pip
			+		Line Proposed Conto Line Proposed Storm Conveyance Pip Existing Preserve
			+		Line Proposed Conto Line Proposed Storm Conveyance Pip Existing Preserve
			+		Line Proposed Conto Line Proposed Storm Conveyance Pip Existing Preserve Existing Tree Cat Counted Toward Stormwater Req
			+		Line Proposed Conto Line Proposed Storm Conveyance Pip Existing Preserve Existing Tree Car Counted Toward Stormwater Requ Preserved Canop
					Line Proposed Conto Line Proposed Storm Conveyance Pipe Existing Preserve Existing Tree Car Counted Toward Stormwater Requ Preserved Canop Limits
					Line Proposed Conto Line Proposed Storm Conveyance Pip Existing Preserve Existing Tree Can Counted Toward Stormwater Req Preserved Canop Limits
					Line Proposed Contc Line Proposed Storm Conveyance Pip Existing Preserve Existing Tree Ca Counted Toward Stormwater Req Preserved Canop Limits
					Line Proposed Conto Line Proposed Storm Conveyance Pip Existing Preserve Existing Tree Cal Counted Toward Stormwater Req Preserved Canop Limits
					Line Proposed Conto Line Proposed Storm Conveyance Pip Existing Preserve Existing Tree Car Counted Toward Stormwater Req Preserved Canop Limits
					Line Proposed Conto Line Proposed Storm Conveyance Pip Existing Preserve Existing Tree Car Counted Toward Stormwater Req Preserved Canop Limits
					Line Proposed Contc Line Proposed Storm Conveyance Pip Existing Preserve Existing Tree Ca Counted Toward Stormwater Req Preserved Cano Limits
					Line Proposed Contc Line Proposed Storm Conveyance Pip Existing Preserve Existing Tree Ca Counted Toward Stormwater Req Preserved Cano Limits
					Line Proposed Contc Line Proposed Storm Conveyance Pip Existing Preserve Existing Tree Cal Counted Toward Stormwater Req Preserved Canop Limits
					Line Proposed Contc Line Proposed Storm Conveyance Pip Existing Preserve Existing Tree Ca Counted Toward Stormwater Req Preserved Canop Limits
					Line Proposed Conto Line Proposed Storm Conveyance Pip Existing Preserve Existing Tree Ca Counted Toward Stormwater Req Preserved Canop Limits
					Line Proposed Conto Line Proposed Storm Conveyance Pip Existing Preserve Existing Tree Can Counted Toward Stormwater Requ Preserved Canop Limits
					Line Proposed Conto Line Proposed Storm Conveyance Pip Existing Preserve Existing Tree Car Counted Toward Stormwater Requ Preserved Canop Limits
					Line Proposed Conto Line Proposed Storm Conveyance Pipe Existing Preserve Existing Tree Car Counted Toward Stormwater Requ Preserved Canop Limits
PLANT SCHEDULE					Line Proposed Conto Line Proposed Storm Conveyance Pipe Existing Preserve Existing Tree Car Counted Toward Stormwater Requ Preserved Canop Limits
PLANT SCHEDULE QTY. SYM. SCIENTIFIC NAME DECIDUOUS TREES	COMMON NAME	CAL. SIZE	ROOT	SPACING COMMENTS	Line Proposed Contor Line Proposed Storm Conveyance Pipe Existing Preserve Existing Tree Car Counted Toward Stormwater Requ Preserved Canop Limits
PLANT SCHEDULE QTY. SYM. SCIENTIFIC NAME DECIDUOUS TREES 5 AR 4 AS Acer saccharum 'Commemoration'	COMMON NAME	CAL. SIZE	ROOT B&B B&B	SPACING COMMENTS	Line Proposed Conto Line Proposed Storm Conveyance Pip Existing Preserve Existing Tree Car Counted Toward Stormwater Requ Preserved Canop Limits COMPLIANC NATIVE, Plum stead Pl
PLANT SCHEDULE QTY. SYM. SCIENTIFIC NAME DECIDUOUS TREES 5 AR Acer rubrum 4 AS Acer saccharum 'Commemoration' EVERGREEN TREES 15 IO 10 I/ex opaca 'Greenleaf'	COMMON NAME	CAL. SIZE	ROOT B&B B&B B&B B&B	SPACING COMMENTS	Line Proposed Contc Line Proposed Storm Conveyance Pip Existing Preserve Existing Tree Ca Counted Toward Stormwater Req Preserved Cano Limits COMPLIANC NATIVE, Plum stead P NATIVE, Plum stead P
PLANT SCHEDULE QTY. SYM. SCIENTIFIC NAME DECIDUOUS TREES 5 AR Acer rubrum 4 AS Acer saccharum 'Commemoration' EVERGREEN TREES 15 IO Ilex opaca 'Greenleaf' 3 JV Juniperus virginiana 'Brodie'	COMMON NAME Red Maple Common oration Sugar Maple Greenleaf American Holly Brodie Eastern Red Cedar	CAL. SIZE	ROOT B&B B&B B&B B&B	SPACING COMMENTS	Line Proposed Contc Line Proposed Storm Conveyance Pip Existing Preserve Existing Tree Ca Counted Towarc Stormwater Req Preserved Cano Limits COMPLIANC NATIVE, Plum stead P NATIVE, Plum stead P NATIVE
PLANT SCHEDULE QTY. SYM. SCIENTIFIC NAME DECIDUOUS TREES S AR Acer rubrum 4 AS Acer saccharum 'Commemoration' EVERGREEN TREES S AR Acer saccharum 'Commemoration' EVERGREEN TREES 15 Ibro Juex opaca 'Greenleaf' 1 3 JV Juniperus virginiana 'Brodie' 1	COMMON NAME Red Maple Comemoration Sugar Maple Greenleaf American Holly Brodie Eastern Red Cedar	CAL. SIZE 2 1/2"-3" 12'-14' 2 1/2"-3" 12'-14' 6-8' 6-8'	ROOT B&B B&B B&B B&B	SPACING COMMENTS SPACING COMMENTS	Line Proposed Contc Line Proposed Storm Conveyance Pip Existing Preserve Existing Tree Ca Counted Towarc Stormwater Req Preserved Cano Limits COMPLIANC NATIVE, Plum stead P NATIVE, Plum stead P NATIVE
PLANT SCHEDULE QTY. SYM. SCIENTIFIC NAME DECIDUOUS TREES 5 A.R. Acer rubrum 4 AS Acer saccharum 'Commemoration' EVERGREEN TREES 15 10 Itex opaca 'Greenleaf' 3 JV Juniperus virginiana 'Brodie'	COMMON NAME Red Maple 2 Comemoration Sugar Maple 2 Greenleaf American Holly 3 Brodie Eastern Red Cedar 3	CAL. SIZE	ROOT B&B B&B B&B B&B	SPACING COMMENTS	Line Proposed Contc Line Proposed Storm Conveyance Pip Existing Preserve Existing Tree Ca Counted Towarc Stormwater Req Preserved Cano Limits COMPLIANC NATIVE, Plum stead P NATIVE, Plum stead P NATIVE
PLANT SCHEDULE QTY. SYM. SCIENTIFIC NAME DECIDUOUS TREES S AR Acer rubrum 4 AS Acer saccharum 'Commemoration' EVERGREEN TREES S AR Acer saccharum 'Commemoration' EVERGREEN TREES 15 IO Ilex opaca 'Greenleaf' 3 3 JV Juniperus virginiana 'Brodie' S	COMMON NAME Red Maple ? Comemoration Sugar Maple ? Greenleaf American Holly ? Brodie Eastern Red Cedar ?	CAL. SIZE	ROOT B&B B&B B&B B&B	SPACING COMMENTS	Line Proposed Contc Line Proposed Storm Conveyance Pip Existing Preserve Existing Tree Ca Counted Towarc Stormwater Req Preserved Cano Limits COMPLIANC NATIVE, Plum stead P NATIVE, Plum stead P NATIVE

1-1-		P 0	D North East
	510 m	"ague Const	an Board
\backslash		Sto Min Road	s Nest Park 500
		SITE	
		Share an even meren and	NO FUI PORT
	<u> </u>	Location Map Scale: 1" = 800'	_
		Legend	
			Existing Right-of-way Existing Property Line Easements
			Existing Building
		<u>195</u>	Existing Index Contour Line Existing Contour Line Existing Over Head Wire
		ی۔st	Existing Utility Pole Existing Storm Sewer
		\bigcirc	Existing Edge of Vegetation
			Existing Sidewalk
			Existing Wall
			Proposed Asphalt Driveway
		495	Proposed Index Contour Line
		491	Proposed Countor Line Proposed Filter Sock
		rs	Proposed Filter Sock Trap
		DS	Proposed Diversion Sock Proposed Soil Stockpile
		LOD	Proposed Limit of Disturbance
			Proposed Rock Construction Entrance
G WATERS'			Proposed Trap Drainage Area
SHAMINY CREEK			
ES (WWF); MIGRATORY FISH (MF)			
TURBANCE: 39,567 SF (0.91 ACRES)			
DISTURBED AREA SOILS INFORMATION	0		
NAMEDESCRIPTIONTOPSOILSEASON/WATER TAWeikert channer silt loam3-8% slopesFair>80"Weikert channer silt loam8-15% slopesFair>80"on silt loam3-8% slopesFair18-36"	AL DEPTH TO DRAINAGE BLE BEDROCK CLASS 20-40" Well Drained 20-40" Well Drained 20-36" Mod. Well Drained		
dential District or 22.14 Acres to Title Line or 21.91 Acres to Legal Right of Way Line 21 59 Acres to Required Right of Way Line			
	Erosi	on & Sediment Control Pla	ลก
Adams (H/W)	40	99 CURLY HILL ROAL	ס
3	PLUMSTEAD	TOWNSHIP, BUCKS COUNTY, COMMONN	VEALTH PA
	NWEA REGISTERED	EUSTACE ENGINEERS I LANDSCAPE ARCHITECTS I SURVEYO	DRAWN BY MWW CHECKED BY
100 200	MARTIN J. EUSTACE, III ENGINEER	ston Road Tel: (215) 346-87 B - 2nd Floor Fax: (215) 346-87 Grove, PA 19090 www.eustaceeng.c	757 759 om <i>DATE</i> 01-05-24
1" = 50' SHEET 7 OF 8	Marte PAL	arta Eustace III tin J. Eustace, III, P.E. ic. PE048891E	DRAWING No. 2383 01 14

EROSION AND SEDIMENT CONTROL NARRATIVE Prepared by : Martin J. Eustace, III., P.E.

Experience: Since 1988 has prepared numerous sedimentation plans for sites up to 700 acres, located in Bradford, Bucks, Chester, Montgomery, Tioga & Philadelphia Counties.

SITE LOCATION

exist.

The project site is located on the North side of Curly Hill Rd in Plumstead Township. Bucks County, Pennsylvania. The site is zoned residentia

SITE DESCRIPTION

The majority of the project site consists of open fields with small areas of internal vegetation, and 4. Hay or straw mulch must be applied at rates of at least 3.0 tons per acre. Straw mulch one existing 3 story Dwelling and one out building. The topography generally falls from north to south toward Curly Hill Road.

The site is located within the Neshaminy Creek watershed and drains to the North Branch of Neshaminy Creek. For the past fifty (50) years the site was used for residential and agricultural purposes. No naturally occurring geologic/soil conditions that have the potential to cause pollution

PROPOSED DEVELOPMENT

The applicant is proposing to subdivide the site and construct a new drive way into the sub-divided lot 2. Access to the site will be provided via the new driveway off of Curly Hill Road. In order to reduce thermal impacts to receiving waters ground level impervious cover shall consist of mostly gravel and shall be kept to the minimum required by the use and proposed impervious surfaces shall be directed to existing vegetated areas. The proposed improvements were located with geologic mapping in mind and to protect the existing vegetation and limit disturbance.

STORMWATER MANAGEMENT

Runoff from both sites and off-site areas drains thru the site to an existing drainage ditch located on the north side of Curly Hill Road. Stormwater is conveyed under the road via an existing storm pipe where it ultimately drains to the North Branch of the Neshaminy Creek.

Runoff from the proposed improvements will be conveyed via new grading to compost filter soc and into a compost sock sediment trap thru the construction phase of the project

Water guality and volume reduction requirements shall be met with the use of non-structural BMPs which include preserving and planting trees near the proposed impervious areas.

PROPOSED EROSION AND SEDIMENT CONTROL

During the earthmoving period, we propose to control erosion and sedimentation by use of a rock construction entrance, compost filter sock, rock filter and sock traps. Before any excavation begins, all perimeter silt sock shall be installed parallel to existing grade, as illustrated on the plans. All sedimentation control measures pertaining to the areas intended to be disturbed shall be installed and stabilized at once. Efforts shall be made to maximize protection of existing vegetation by installing the compost filter socks prior to beginning excavation

To limit the extent and duration of earth disturbance only that portion of the site that is to receive improvements shall be stripped of all vegetation and topsoil that may be present. The topsoil required for redistribution will be stockpiled, seeded and mulched immediately and protected by compost filter sock All newly graded slopes of 3.1 and steeper shall be covered immediately with appropriate erosion control blankets. To the greatest extent possible, the contractor shall utilize construction methods that limit soil compaction during construction

Until the site is stabilized, all erosion and sedimentation controls must be maintained properly Maintenance will include inspection of all erosion and sedimentation control facilities after each storm event and on a daily basis. All preventative and remedial maintenance work, including clean out, repair, replacement, regrading, reseeding, remulching and renetting will be performed immediately. The Owner's representative in charge of the project will be responsible for the implementation of this sedimentation control plan and the maintenance of all facilities until the project is fully stabilized.

Stabilization of slopes and lawns shall consist of a permanent type of seeding or sodding, and will 4. be conducted in accordance with the applicable Soil Conservation Service Specifications. Final stabilization measures of the site shall be completed immediately after this project has been fully completed. Other measures that help prevent or minimize generation of increased stormwater runoff during construction include proper sequencing and maintenance of temporary facilities.

DEFINITIONS

If the site will need to import or export material from the site, the responsibility for performing environmental due diligence and determination of clean fill will rest with the contractor.

Clean Fill is defined as: Uncontaminated, non-water soluble, non-decomposable, inert, solid material. The term includes soil, rock, stone, dredged material, used asphalt, and brick, block or concrete from construction and demolition activities that is separate from other waste and is recognizable as such. The term does not include materials placed in or on the waters of the nwealth unless otherwise authorized. (The term "used asphalt" does not include milled asphalt or asphalt that has been processed for re-use).

Clean Fill affected by a spill or release of a regulated substance: Fill materials affected by a spill or release of a regulated substance still qualifies as clean fill provided the testing reveals that the fill material contains concentrations of regulated substances that are below the residential limits in Tables FP-1a and FP-1b found in the Department's policy "Management of Fill"

Any person placing clean fill that has been affected by a spill or release of a regulated substance must use form FP-001 to certify the origin of the fill material and the results of the analytical testing to qualify the material as clean fill. Form FP-001 must be retained by the owner of the property receiving the fill. A copy of Form FP-001 can be found at the end of these instructions.

Environmental due diligence: The applicant must perform environmental due diligence to determine if the fill materials associated with the project qualify as clean fill. Environmental due diligence is defined as: Investigative techniques, including, but not limited to, visual property inspections, electronic data base searches, review of property ownership, review of property use history, Sanborn maps, environmental questionnaires, transaction screens, analytical testing, environmental assessments or audits. Analytical testing is not a required part of due diligence unless visual inspection and/or review of the past land use of the property indicates that the fill may have been subjected to a spill or release of regulated substance. If the fill may have been affected by a spill or release of a regulated substance, it must be tested to determine if it qualifies as clean fill. Testing should be performed in accordance with Appendix A of the Department's policy "Management of Fill".

Fill material that does not qualify as clean fill is regulated fill. Regulated fill is waste and must be managed in accordance with the Department's municipal or residual waste regulations based on 25 Pa. Code Chapters 287 Residual Waste Management or 271 Municipal Waste Management, whichever is applicable. These regulations are available on-line at www.pacode.com.

MAINTENANCE PROGRAM

The contractor shall check the erosion and sedimentation control facilities once daily, prior to any anticipated rainfall events, and after every runoff event. Sediment barriers shall be maintained in good repair, remove silt build up per detail, spread and stabilize on site. Seeded areas that washed away shall be filled and graded as necessary and then reseeded and mulched. Where sediment barrier has been washed out by concentrated runoff, repair fencing and provide rock filter berm backing to fencing to a depth of 2' by 20' wide. Inlet Filter Bags shall be emptied and rinsed or replaced when half full or when flow capacity has been reduced so as to cause flooding by bypassing the inlet. Inspections must be logged onto DEP form 3150-FM-BWEW0083, dated 2/2012 and kept on site at all times.

TOPSOIL APPLICATION NOTES

Graded areas should be scarified or otherwise loosened to a depth of 3 to 5 inches to permit bonding of the topsoil to the surface areas and to provide a roughened surface to prevent topsoil from sliding down slope.

Topsoil should be uniformly distributed across the disturbed area to a depth of 4 to 8 inches \minimum - 2 inches on fill outslopes. Spreading should be done in such a manner that sodding or seeding can proceed with a minimum of additional preparation or tillage. Irregularities in the surface resulting from topsoil placement should be corrected in order to prevent formation of depressions unless such depressions are part of the PCSM plan.

Topsoil should not be placed while the topsoil or subsoil is in a frozen or muddy condition, when the subsoil is excessively wet, or in a condition that may otherwise be detrimental to proper grading and seedbed preparation. Compacted soils should be scarified 6 to 12 inches along contour wherever possible prior to seeding **TABLE 11.1**

Cubic Yards of Topsoil Required for Application to Various Depths Depth (in) Per 1,000 Square Feet Per Acre 3.1 134 6.2 268 9.3 403 537 12.4 4 15.5 672 5 18.6 6 806 21.7 940 24.8 1.074 8

STABILIZATION NOTES

Stockpile heights must not exceed 35'. Stockpile slopes must be 2:1 or flatter.

- Upon completion of an earth disturbance activity or any stage or phase of an activity, the operator shall stabilize immediately the disturbed areas to protect from accelerated erosion. During non-germinating periods, mulch must be applied at the specified rates. Disturbed areas which are not at finished grade and which will be redisturbed within 1 year may be stabilized in accordance with temporary seeding specifications. Disturbed areas, which are either at finished grade or will not be redisturbed within 1 year, must be stabilized in accordance with permanent seeding specifications.
- Stockpiles must be stabilized immediately.
- should be applied in long strands, not chopped or finely broker
- 5 Until the site has achieved final stabilization the owner and/or contractor shall properly implement, operate and maintain all the best management practices. Maintenance shall include inspections of all erosion and sedimentation control after each runoff event and on a weekly basis. All site inspections will be documented in an inspection log kept for this purpose, including the compliance actions and the date, time, and name of the person conducting the inspection. The inspection log will be kept on site at all times and made available to the DCCD and DEP upon request
- 6. Site inspections and maintenance of all BMP's shall be conducted weekly, after every runoff event and also prior to any anticipated precipitation events. All site inspections will be documented in an inspection log kept for this purpose, including the compliance actions and the date, time, and name of the person conducting the inspection. The inspection log will be kept on site at all times and made available to the DCCD and DEP upon request.
- All preventative and remedial maintenance work, including clean out, repair, replacement, regrading, reseeding, remulching, and renetting, must be performed immediately. If erosion and sediment BMPs fail to perform as expected, replacement BMPs or modifications of those installed will be needed.
- 8. Where BMPs are found to fail to alleviate erosion and sediment pollution, the permittee shall include the following informatio The location and severity of the BMP's failure and any pollution events All steps taken to reduce, eliminate, and prevent the recurrence of the
- non-compliance. The time frame to correct the non-compliance, including the exact dates when
- the activity will return to compliance
- After final site stabilization has been achieved, temporary erosion and sediment BMPs must be removed. Areas disturbed during removal of the BMPs must be stabilized immediately.
- 10. An area shall be considered to have achieved final stabilization when it has a minimum of 0% uniform perennial vegetative cover or other permanent non-vegetative cover with a density sufficient to resist accelerated surface erosion and subsurface characteristics sufficient to resist sliding or other movements.

11. Erosion control blankets must be installed on all slopes 3:1 or greater.

CONSTRUCTION SEQUENCE

All earth disturbance activities shall proceed in accordance with the following sequence. Each stage shall be completed in compliance with Chapter 102 regulations before any following stage is initiated. Clearing and grubbing shall be limited only to those areas described in each stage.

- At least 7 days before starting any earth disturbance activities, the operator shall invite all contractors involved in those activities, the landowner, all appropriate municipal officials, the erosion and sediment control preparer, and a representative of the Bucks County Conservation District to schedule an on-site meeting. The contractor shall verify locations and depths of all existing utilities prior to start of work.
- At least 3 days before starting any earth disturbance activities, all contractors involved in those activities shall notify the Pennsylvania One Call System Incorporated at 1-800-242-1776 for buried utilities locations.
- The contractor shall notify the Township and Township Engineer 48 hours prior to the start of construction
- Before implementing any revisions to the approved erosion and sediment control plan, or revisions to other plans which may affect the effectiveness of the approved E&S control plan, the operator must receive the approval of the revisions from the Bucks County Conservation The operator shall remove from the site, recycle or dispose of all building materials and
- wastes in accordance with the Department's Solid Waste Management Regulations at 25 PA Code 260.1 et seq., 271.1 et seq.

Prior to construction, stake out the limit of disturbance.

- No more than 15,000 square feet of disturbed area shall reach final grade before initiating seeding and mulching operations
- Cessation of activity for 4 days or longer requires temporary stabilization Install rock construction entrance and diversion socks as shown on the plans.
- Install compost sock sediment traps.
- Strip and stockpile topsoil from area of the access drive beginning at Curly Hill Road.
- Surround stockpile with compost filter sock and stabilize immediately with temporary seed. 12. Grade in the area of access drive and immediately stabilize with permanent stabilization. Stabilize disturbed areas with permanent seeding and mulch and/or place erosion blankets
- on all slopes 3:1 or steeper along with permanent lining as noted on plans. 13. Construct asphalt and gravel base courses immediately
- 14. Install trench drain with headwall and endwall. Protect grate with compost filter sock where
- necessary. Contractor shall remove any sediment that accumulates within trench drain. Perform final site grading where necessary. Install asphalt wearing course and gravel surface course on driveway. Install lawns and landscape beds, permanent seeding, landscaping and
- Remove any accumulated sediment from sock traps and stabilize elsewhere on site.
- Contact Bucks County Conservation District once 70% uniform perennial cover is reached
- and before any BMP's are removed. 18. Remove temporary erosion control measures, including compost filter sock traps after all disturbed areas are stabilized with a minimum of 80% vegetative cover. Re-stabilize all areas
- disturbed due to the removal of temporary erosion control facilities 19. Once compost filter sock trap is removed, the area should be stabilized with erosion control
-). Immediately upon discovering unforeseen circumstances posing the potential for accelerated

erosion and/or sediment pollution, the operator shall implement appropriate best management practices to eliminate potential for accelerated erosion and/or sediment pollution.31. Within 30 days after the completion of earth disturbance activities authorized by the permit, including the permanent stabilization of the site and proper installation of PCSM BMP's in accordance with the approved PCSM plan, or upon submission of the NOT if sooner, the permittee shall file with the department or authorized conservation district a stated signed by a licensed professional and by the permittee certifying that work has been performed in accordance with the terms and conditions of this permit and approved E&S and PCSM Plans. See BMP Construction sequence on PCSM Plan for critical stages.

PROPOSED TEMPORARY SEEDING

100% Perennial Ryegrass Pure Live Seed: 81%

Rate: 1 Lbs. per 1,000 s.f. = 0.02 Tons/Ac Provide clean mulch on all seeded areas.

- Fertilizer: 12.5 Lbs. per 1.000 s.f. / 10-10-10 Equiv. = 0.25 Tons/Ac
- Lime: 40 Lbs. per 1.000 s.f. = 1 Tons/Ac Straw Mulch: 140 Lbs. per 1,000 s.f. = 3 Tons/Ac. Provide clean, unchopped or not finely broken straw mulch on all
- seeded areas that are not blanketed. Straw should be either wheat or oat straw.
- Anchor Material: Organic Guar-gum Based Tackifier Anchoring Method: Per manufacturer's recommendation. Preferably apply straw and tackifier at the same time.
- Anchoring Rate: Per manufacturer's recommendation. (Typ. 20-40 lbs per Acre)

PROPOSED PERMANENT SEEDING/SOD FOR LAWN AREAS

80% Turf Type Tall Fescue (3 dark green drought tolerant varieties min.) 10% Kentucky Bluegrass (drought tolerant variety) 10% Turf Type Perennial Ryegrass Rate: 6 Lbs. Per 1,000 s.f. = 262 lbs/Ac. Fertilizer: 25 Lbs./1,000 s.f./10-20-20 Equiv. = 0.50 Tons/Ac.

Lime 240 Lbs./1.000 s.f. = 6 Tons/Ac Straw mulch: 140 Lbs./1,000 s.f. = 3 Tons/Ad

Provide clean, unchopped or not finely broken straw mulch on all seeded areas that are not blanketed. Straw should be either wheat or oat straw. Anchor Material: Organic Guar-gum Based Tackifier Anchoring Method: Per manufacturer's recommendation. Preferably apply

straw and tackifier at the same time. Anchoring Rate: Per manufacturer's recommendation. (Typ. 20-40 lbs per Acre)

PROPOSED PERMANENT SEEDING FOR

STEEP SLOPES

- Ernst Seed Co. Mix #187 "Native Steep Slopes Mix with Annual Rye Grass'
- Rate: 1.5 lb. per 1000 s.f.
- Fertilizer: 25 Lbs./1,000 s.f./10-20-20 Equiv. = 0.50 Tons/Ac. Lime: 240 lb. per 1000 s.f. = 6 Tons/Ac
- Mulch: Clean Straw 140 lb. per 1000 s.f. = 3 Tons/Ac. Provide clean, unchopped or not finely broken straw mulch on all seeded areas that are not blanketed. Straw should be either wheat or oat straw. Anchor Material: Organic Guar-gum Based Tackifier
- Anchoring Method: Per manufacturer's recommendation. Preferably apply straw and tackifier at the same time.
- Anchoring Rate: Per manufacturer's recommendation. (Typ. 20-40 lbs per Acre)

SEDIMENTATION CONTROL NOTES

- 4. A copy of the approved erosion and sediment control plan must be available at the project site at all times
- Protection, Subpart C, Protection of Natural Resources, Article III, Water Resources, Chapter 102, Erosion Control.
- BCCD to an on-site meeting.
- 1-800-242-1776 for buried utilities locations. SN 1966822
- or by the Department prior to implementation.
- fenced off before clearing and grubbing operations begin
- and completely implemented.
- 11. Erosion and sediment BMP's must be constructed, stabilized and functional before site disturbance begins within the tributary areas of those BMP's.

be required

immediately.

3:1 or steeper

topsoil stockpiles.

earth surfaces.

Water Act.

% Purity

% Pure Live Seed

eeding Season

opsoil Placement Dep

coordinate remediation measures

disposing of wastes at a proper site.

Compost filter socks must be installed at level grade. Both ends of each sock section must be

rock filter outlet. See Rock Filter Detail.

Erosion and sedimentation control shall be conducted in accordance with the Bucks County

Soil Conservation District Standards Before initiating any revisions to the approved erosion and sediment control plan or revisions to others plans which may affect the effectiveness of the approved E&S control plan, the operator must receive approval of the revisions from the Bucks County Conservation District

3. The operator shall assure that an erosion and sediment control plan has been prepared. approved by the appropriate Conservation District, and is being implemented and maintained for all soil and/or rock spoil and borrow areas, regardless of their locations.

The contractor is advised to become thoroughly familiar with the provisions of the Appendix 64, Erosion Control Rules and Regulations, Title 25, Part 1, Department of Environmental

6 At least 7 days before starting any earth disturbance activities including clearing and grubbing, the operator shall invite all contractors involved in those activities, the landowner all appropriate municipal officials, the erosion and sediment control plan preparer, and the

At least 3 days before starting any earth disturbance activities, all contractors involved in those activities shall notify the Pennsylvania One Call System Incorporated at

All earth disturbance activities shall proceed in accordance with the sequence provided on the plan drawings. Deviation from that sequence must be approved in writing from the BCCD

At no time shall construction vehicles be allowed to enter areas outside the limit of disturbance boundaries shown on the plan maps. These areas must be clearly marked and

10. The operator shall assure that the approved erosion and sediment control plan is properly

extended at least 10 feet up slope at 45 degrees to the main barrier alignment. 13. Any sock section which has been undermined or topped must be immediately replaced with a

14. Sediment must be removed when accumulations reach half the ground height of the barrier.

15. Sediment must be removed from storm water inlet protection after each runoff event. 16. Storm water inlets must be protected until the tributary areas have been stabilized.

Stockpile height must not exceed 35 feet. Stockpile slopes must be 2:1 or flatter. [E&SPCPM

Immediately after earth disturbance activities cease, the operator shall stabilize any areas

must be stabilized in accordance with the permanent vegetative stabilization specifications.

BMP's fail to perform as expected, replacement BMP's, or modifications to those installed will

distrubed by the activities. During non-germinating periods, mulch must be applied at the recommended rates. Disturbed areas which are not at finished grade and will be redisturbed within one year may be stabilized in accordance with temporary seeding specifications. Disturbed areas which are at finished grade or which will not be redisturbed within one year

Until the site achieves final stabilization, the permitee shall assure that the best managemen practices are implemented, operated, and maintained properly and completely. Maintenance shall include inspections of all best management practice facilities and maintain and make available to the Bucks County Conservation District complete, written inspection logs of all those inspections. All maintenance work, including cleaning, repair, replacement, regrading reseeding, and renetting must be performed immediately. If erosion and sediment control

20. An area shall be considered to have achieved final stabilization when it has a minimum uniform 70% perennial vegetative cover or other permanent non-vegetative with a density sufficient to resist accelerated surface erosion and subsurface characteristics sufficient to resist sliding and other movements. Cut and fill slopes shall be capable of resisting failure due to slumping, sliding, or other movements.

21. After final site stabilization has been achieved, temporary erosion and sedimentation controls must be removed. Areas disturbed during removal of the BMP's must be stabilized

22. Immediately upon discovering unforeseen circumstances posing the potential for accelerated erosion and/or sediment pollution, the operator shall implement appropriate best management practices to eliminate potential for accelerated erosion and/or sediment pollution and notify the local conservation district and/or the regional office of the Department

23. Mulch with mulch control netting or erosion control blankets should be installed on all slopes Straw mulch should be applied in long strands, not chopped or finely broken.

25. All building materials and wastes shall be removed from the site, recycle, or dispose of in accordance with the Department's Solid Waste Management Regulations at 25 Pa. Code 260.1 et seq., 271.1 et seq., and 287.1 et seq. No building materials or wastes or unused building materials shall be burned, buried, dumped or discharged at the site

26. All off-site waste and borrow areas must have E&S plan approval by the local conservation district or the Department fully implemented prior to being activated

The contractor is responsible for ensuring that any material brought on site is clean fill. Form FP-001 must be retained by the property owner for any fill material affected by a spill or release of regulated substance by gualifying as clean fill due to analytical testing.

28. Sediment removed from BMP's shall be disposed of in landscape areas outside of steep slopes, wetlands, floodplains or drainage swales and immediately stabilized, or placed in

29. Six inches (6") of topsoil cover is to be provided, after settlement, over all the site's exposed

31. Should severe ground water conditions be encountered during construction activities tha affect the erosion and sedimentation control measures, the geotechnical engineer shall

32. All pumping of sediment laden water shall be through a sediment control BMP, such as a pumped water filter bag discharging over non-disturbed areas.

Owner/Operator shall inspect all stormwater conveyance pipes, inlets, and water quality inlets regularly and clean at least twice a year to remove sediment, accumulated oil and grease, floatables, and other pollutants. Sediment should be removed from skimmer structures less frequently but the structures still must be inspected periodically. Wastes removed from the systems should be tested to determine proper disposal methods. The wastes may be hazardous; therefore, maintenance costs should be budgeted to include

34. The erosion and sediment control plan must display a PA ONE CALL SYSTEM INCORPORATED symbol including the site identification number

30. Winter earth moving activities shall be monitored by a geotechnical engineer.

35. Until the site is stabilized, all erosion and sediment BMPs must be maintained properly. Maintenance must include inspections of all erosion and sediment control BMPs after each runoff event and on a weekly basis. All preventative and remedial maintenance work, including clean out repair, replacement, regrading, reseeding, and renetting must be performed immediately. If erosion and sediment control BMPs fail to perform as expected. replacement BMPs, or modifications to those installed will be required.

36. At the end of each working day, any sediment tracked or conveyed onto a public roadway will be removed and redeposited onto the construction site. Removal can be completed through use of mechanical or hand tools. but must never be washed, shoveled, or swept into any roadside ditch, storm sewer or surface water

37. Before initiating any revisions to the approved erosion and sediment control plan or revisions to others plans which may affect the effectiveness of the approved E&S control plan, the operator must receive approval of the revisions from the Montgomery County Conservation

38. Erosion and sediment BMP's must be constructed, stabilized, and functional before site disturbance begins within the tributary areas of those BMP's. E&SPCPM p. 168

39. Permittees and copermittees are responsible for ensuring that a licensed professional have oversight responsibilities for the design and proper installation of BMPs identified in the PCSM Plan prior to the submission of the NOT for this permit. The licensed professional shall certify that the BMPs identified in the plan have been installed in accordance with the approved plan The installation schedule of PCSM BMPs and maintenance requirements contained within the approved PCSM Plan must be followed; and failure to comply with the installation schedule is a violation of this permit, the Clean Streams Law, and the Clean

40. Upon the installation or stabilization of all perimeter sediment control BMPs and at least 3 days prior to proceeding with the bulk earth disturbance activities, the permittee or co-permittee shall provide notification to the department or authorized conservation district.

41. Failure to correctly install E&S BMPs, failure to prevent sediment-laden runoff from leaving the construction site, or failure to take immediate corrective action to resolve failure of E&S BMPs may result in administrative, civil, and/or criminal penalties being instituted by the Department as defined in Section 602 of the PA Clean Streams Law. The Clean Streams Law provides for up to \$10,000 per day civil penalties, up to \$10,000 in summary criminal penalties and up to \$25,000 in misdemeanor criminal penalties for each violation.

eding
e 15
mber 1
e

Te

Spring

MOUNTABLE BERM SHALL BE INSTALLED WHEREVER OPTIONAL CUI VERT PIPE IS USED AND PROPER PIPE COVER AS SPECIFIED BY MANUFACTURER IS NOT

MAINTENANCE: ROCK CONSTRUCTION ENTRANCE THINKNESS SHALL BE CONSTANTLY MAINTAINED TO THE SPECIFIED DIMENSIONS BY ADDING ROCK. A STOCKPILE SHALL BE MAINTAINED ON SITE FOR THIS PURPOSE ALL SEDIMENT DEPOSITED ON PAVED ROADWAYS SHALL BE REMOVED AND RETURNED TO THE CONSTRUCTION SITE IMMEDIATELY. IF EXCESSIVE AMOUNTS OF SEDIMENT ARE

OCATION	DRAINAGE AREA	PROVIDED VOLUME
OPERTY LINE	0.09 Acres	200 CuFt

